

AHComputing Roofing Estimates

Powered by AI Roof Analysis
hire.ahcomputing.com

ROOFING
ESTIMATE

BILL TO
Property Owner
1612 S Canton Ave
Springfield, MO 65802

Estimate # RE-202605-1504
Estimate Date 05-08-2026
Valid Until 05-22-2026

Roof Area 2757 sqft	Squares 27.6	Eave Length 158 Inft	Ridge/Hip 30 Inft	Roof Type Hip	Pitch medium (7/12)	AI Confidence High
---------------------	--------------	----------------------	-------------------	---------------	---------------------	--------------------

QTY	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
94	bundles	Architectural Roofing Shingles	\$48.00	\$4,512.00
8	rolls	Roofing Underlayment (15lb felt, 400 sqft/roll)	\$75.00	\$600.00
474	sqft	Ice & Water Shield (eave protection)	\$0.75	\$355.50
158	Inft	Drip Edge / Eave Trim	\$1.50	\$237.00
30	Inft	Ridge Cap Shingles (ridge + hips)	\$3.50	\$105.00
4	Inft	Valley Flashing	\$4.00	\$16.00
69	lbs	Roofing Nails	\$3.50	\$241.50
27.6	squares	Tear-Off & Disposal (existing roof removal)	\$65.00	\$1,794.00
27.6	squares	Installation Labor	\$150.00	\$4,140.00

Subtotal \$12,001.00

Sales Tax (8%) \$960.08

TOTAL (USD)	\$12,961.08
--------------------	--------------------

Estimator Notes: Solar API data: 8 roof segments, avg pitch 31.4° (7/12), imagery from 2022-06. Quality: HIGH.

Terms & Conditions: This estimate is valid for 30 days. A 50% deposit is required to begin work. Final invoice may vary +/-10% based on field conditions. All work performed to local building code. Permit costs not included.

Contractor Signature: _____ Customer Signature: _____

Roof Analysis & Calculation Detail

Estimate RE-202605-1504 | 1612 S Canton Ave, Springfield, MO 65802

SATELLITE IMAGE



Zoom 20 | 0.0595 m/px
640x640px | Google Maps Static API
Lat 37.18609

ROOF PLANE BREAKDOWN

PLANE	FOOTPRINT	PITCH	MULT	ADJ AREA
North-facing slope	616 sqft	7/12	x1.1719	721.9 sqft
East-facing slope	497 sqft	7/12	x1.1694	581.2 sqft
South-facing slope	446 sqft	7/12	x1.1623	518.4 sqft
West-facing slope	300 sqft	7/12	x1.1671	350.1 sqft
South-facing slope	186 sqft	7/12	x1.1729	218.2 sqft
West-facing slope	174 sqft	7/12	x1.1397	198.3 sqft
West-facing slope	173 sqft	9/12	x1.2709	219.9 sqft
North-facing slope	154 sqft	7/12	x1.1627	179.1 sqft

Footprint total: 2,546 sqft | Avg multiplier: 1.083 | Adjusted area: 2,757 sqft

Calculation Detail — Show Your Work

ITEM	FORMULA
Adjusted area (waste)	$2,757 \text{ sqft} \times (1 + 12\% \text{ waste}) = 3,087.8 \text{ sqft}$
Shingle bundles	$3,087.8 \text{ sqft} / 33 \text{ sqft/bundle} = 93.6 \rightarrow 94 \text{ bundles (ceiling)}$
Underlayment rolls	$3,087.8 \text{ sqft} / 400 \text{ sqft/roll} = 7.72 \rightarrow 8 \text{ rolls (ceiling)}$
Ice & water shield	$\text{Eave } 158 \text{ lnft} \times 3 \text{ ft protection band} = 474 \text{ sqft}$
Drip edge	$\text{Eave perimeter} = 158 \text{ lnft}$
Ridge cap	$\text{Ridge} + \text{hips} = 30 \text{ lnft}$
Valley flashing	$\text{Valley length} = 4 \text{ lnft}$
Roofing nails	$27.6 \text{ squares} \times 2.5 \text{ lbs/sq} = 69.0 \rightarrow 69 \text{ lbs (ceiling)}$
Labor (squares)	$2,757 \text{ sqft} / 100 = 27.6 \text{ squares}$
Sales tax	$\text{Subtotal } \$12,001.00 \times 8\% = \960.08

Google Solar API — Measurement Method

Roof measurements provided by the Google Solar API (buildingInsights endpoint). Google's Solar API uses high-resolution aerial imagery and machine learning to map individual roof segments with measured pitch, area, and orientation. Data covers 8 roof segment(s). Imagery date: 2022-06. Imagery quality: HIGH. Total roof area 2,757 sqft and pitch data are directly measured values, not estimates — no shadow inference required.

Note: Solar API data reflects the most recent available aerial imagery for this property. Linear measurements (eave, ridge, valley) are estimated from segment geometry. A licensed contractor should verify quantities during physical inspection.