

AHComputing Roofing Estimates

Powered by AI Roof Analysis
hire.ahcomputing.com

ROOFING
ESTIMATE

BILL TO

Property Owner

6310 Laguna Bay Court
Houston, TX 77041

Estimate # RE-202605-8419
Estimate Date 05-08-2026
Valid Until 05-22-2026

Roof Area 4186 sqft	Squares 41.9	Eave Length 189 Inft	Ridge/Hip 37 Inft	Roof Type Hip	Pitch medium-steep (8/12)	AI Confidence High
---------------------	--------------	----------------------	-------------------	---------------	---------------------------	--------------------

QTY	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
143	bundles	Architectural Roofing Shingles	\$48.00	\$6,864.00
12	rolls	Roofing Underlayment (15lb felt, 400 sqft/roll)	\$75.00	\$900.00
567	sqft	Ice & Water Shield (eave protection)	\$0.75	\$425.25
189	Inft	Drip Edge / Eave Trim	\$1.50	\$283.50
37	Inft	Ridge Cap Shingles (ridge + hips)	\$3.50	\$129.50
5	Inft	Valley Flashing	\$4.00	\$20.00
105	lbs	Roofing Nails	\$3.50	\$367.50
41.9	squares	Tear-Off & Disposal (existing roof removal)	\$65.00	\$2,723.50
41.9	squares	Installation Labor	\$150.00	\$6,285.00

Subtotal \$17,998.25
Sales Tax (8%) \$1,439.86

TOTAL (USD)	\$19,438.11
-------------	-------------

Estimator Notes: Solar API data: 7 roof segments, avg pitch 35.2° (8/12), imagery from 2023-04. Quality: HIGH.

Terms & Conditions: This estimate is valid for 30 days. A 50% deposit is required to begin work. Final invoice may vary +/-10% based on field conditions. All work performed to local building code. Permit costs not included.

Contractor Signature: _____

Customer Signature: _____

Roof Analysis & Calculation Detail

Estimate RE-202605-8419 | 6310 Laguna Bay Court, Houston, TX 77041

SATELLITE IMAGE



Zoom 20 | 0.0647 m/px
640x640px | Google Maps Static API
Lat 29.86032

ROOF PLANE BREAKDOWN

PLANE	FOOTPRINT	PITCH	MULT	ADJ AREA
East-facing slope	933 sqft	8/12	x1.2127	1,131.4 sqft
West-facing slope	300 sqft	9/12	x1.2487	374.6 sqft
East-facing slope	289 sqft	8/12	x1.2233	353.5 sqft
West-facing slope	269 sqft	8/12	x1.2122	326.1 sqft
South-facing slope	245 sqft	10/12	x1.2899	316.0 sqft
North-facing slope	240 sqft	9/12	x1.2572	301.7 sqft
Southwest-facing slope	213 sqft	7/12	x1.1535	245.7 sqft

Footprint total: 2,489 sqft | Avg multiplier: 1.682 | Adjusted area: 4,186 sqft

Calculation Detail — Show Your Work

ITEM	FORMULA
Adjusted area (waste)	$4,186 \text{ sqft} \times (1 + 12\% \text{ waste}) = 4,688.3 \text{ sqft}$
Shingle bundles	$4,688.3 \text{ sqft} / 33 \text{ sqft/bundle} = 142.1 \rightarrow 143 \text{ bundles (ceiling)}$
Underlayment rolls	$4,688.3 \text{ sqft} / 400 \text{ sqft/roll} = 11.72 \rightarrow 12 \text{ rolls (ceiling)}$
Ice & water shield	$\text{Eave } 189 \text{ lnft} \times 3 \text{ ft protection band} = 567 \text{ sqft}$
Drip edge	$\text{Eave perimeter} = 189 \text{ lnft}$
Ridge cap	$\text{Ridge} + \text{hips} = 37 \text{ lnft}$
Valley flashing	$\text{Valley length} = 5 \text{ lnft}$
Roofing nails	$41.9 \text{ squares} \times 2.5 \text{ lbs/sq} = 104.8 \rightarrow 105 \text{ lbs (ceiling)}$
Labor (squares)	$4,186 \text{ sqft} / 100 = 41.9 \text{ squares}$
Sales tax	$\text{Subtotal } \$17,998.25 \times 8\% = \$1,439.86$

Google Solar API — Measurement Method

Roof measurements provided by the Google Solar API (buildingInsights endpoint). Google's Solar API uses high-resolution aerial imagery and machine learning to map individual roof segments with measured pitch, area, and orientation. Data covers 7 roof segment(s). Imagery date: 2023-04. Imagery quality: HIGH. Total roof area 4,186 sqft and pitch data are directly measured values, not estimates — no shadow inference required.

Note: Solar API data reflects the most recent available aerial imagery for this property. Linear measurements (eave, ridge, valley) are estimated from segment geometry. A licensed contractor should verify quantities during physical inspection.