

AHComputing Roofing Estimates

Powered by AI Roof Analysis
hire.ahcomputing.com

ROOFING
ESTIMATE

BILL TO
Property Owner
3820 E Rosebrier St
Springfield, MO 65809

Estimate # RE-202605-7258
Estimate Date 05-08-2026
Valid Until 05-22-2026

Roof Area 5566 sqft	Squares 55.7	Eave Length 228 Inft	Ridge/Hip 45 Inft	Roof Type Hip	Pitch medium (6/12)	AI Confidence High
---------------------	--------------	----------------------	-------------------	---------------	---------------------	--------------------

QTY	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
189	bundles	Architectural Roofing Shingles	\$48.00	\$9,072.00
16	rolls	Roofing Underlayment (15lb felt, 400 sqft/roll)	\$75.00	\$1,200.00
684	sqft	Ice & Water Shield (eave protection)	\$0.75	\$513.00
228	Inft	Drip Edge / Eave Trim	\$1.50	\$342.00
45	Inft	Ridge Cap Shingles (ridge + hips)	\$3.50	\$157.50
6	Inft	Valley Flashing	\$4.00	\$24.00
140	lbs	Roofing Nails	\$3.50	\$490.00
55.7	squares	Tear-Off & Disposal (existing roof removal)	\$65.00	\$3,620.50
55.7	squares	Installation Labor	\$150.00	\$8,355.00

Subtotal \$23,774.00

Sales Tax (8%) \$1,901.92

TOTAL (USD)	\$25,675.92
--------------------	--------------------

Estimator Notes: Solar API data: 9 roof segments, avg pitch 27.3° (6/12), imagery from 2022-06. Quality: HIGH.

Terms & Conditions: This estimate is valid for 30 days. A 50% deposit is required to begin work. Final invoice may vary +/-10% based on field conditions. All work performed to local building code. Permit costs not included.

Contractor Signature: _____ Customer Signature: _____

Roof Analysis & Calculation Detail

Estimate RE-202605-7258 | 3820 E Rosebrier St, Springfield, MO 65809

SATELLITE IMAGE



Zoom 20 | 0.0595 m/px
640x640px | Google Maps Static API
Lat 37.15969

ROOF PLANE BREAKDOWN

PLANE	FOOTPRINT	PITCH	MULT	ADJ AREA
East-facing slope	1,062 sqft	6/12	x1.1243	1,194.0 sqft
South-facing slope	567 sqft	6/12	x1.1277	639.4 sqft
East-facing slope	489 sqft	6/12	x1.1191	547.2 sqft
West-facing slope	498 sqft	7/12	x1.1475	571.5 sqft
West-facing slope	430 sqft	6/12	x1.1265	484.4 sqft
South-facing slope	375 sqft	7/12	x1.1407	427.8 sqft
North-facing slope	317 sqft	6/12	x1.116	353.8 sqft
North-facing slope	317 sqft	6/12	x1.1128	352.8 sqft
North-facing slope	282 sqft	6/12	x1.1021	310.8 sqft

Footprint total: 4,337 sqft | Avg multiplier: 1.283 | Adjusted area: 5,566 sqft

Calculation Detail — Show Your Work

ITEM	FORMULA
Adjusted area (waste)	$5,566 \text{ sqft} \times (1 + 12\% \text{ waste}) = 6,233.9 \text{ sqft}$
Shingle bundles	$6,233.9 \text{ sqft} / 33 \text{ sqft/bundle} = 188.9 \rightarrow 189 \text{ bundles (ceiling)}$
Underlayment rolls	$6,233.9 \text{ sqft} / 400 \text{ sqft/roll} = 15.58 \rightarrow 16 \text{ rolls (ceiling)}$
Ice & water shield	$\text{Eave } 228 \text{ lnft} \times 3 \text{ ft protection band} = 684 \text{ sqft}$
Drip edge	$\text{Eave perimeter} = 228 \text{ lnft}$
Ridge cap	$\text{Ridge} + \text{hips} = 45 \text{ lnft}$
Valley flashing	$\text{Valley length} = 6 \text{ lnft}$
Roofing nails	$55.7 \text{ squares} \times 2.5 \text{ lbs/sq} = 139.2 \rightarrow 140 \text{ lbs (ceiling)}$
Labor (squares)	$5,566 \text{ sqft} / 100 = 55.7 \text{ squares}$
Sales tax	$\text{Subtotal } \$23,774.00 \times 8\% = \$1,901.92$

Google Solar API — Measurement Method

Roof measurements provided by the Google Solar API (buildingInsights endpoint). Google's Solar API uses high-resolution aerial imagery and machine learning to map individual roof segments with measured pitch, area, and orientation. Data covers 9 roof segment(s). Imagery date: 2022-06. Imagery quality: HIGH. Total roof area 5,566 sqft and pitch data are directly measured values, not estimates — no shadow inference required.

Note: Solar API data reflects the most recent available aerial imagery for this property. Linear measurements (eave, ridge, valley) are estimated from segment geometry. A licensed contractor should verify quantities during physical inspection.